

MINUTE ITEM

4/25/68

38. PROPOSAL OF THE CITY OF LONG BEACH TO EXPEND TIDELAND OIL REVENUES, MARINE STADIUM WEST - LBWO 10,204.

After consideration of Calendar Item 4 attached, and upon motion duly made and unanimously carried, the following resolution was adopted:

THE COMMISSION DETERMINES THAT THE EXPENDITURE PROPOSED AT MARINE STADIUM WEST OF APPROXIMATELY \$37,400 (AS DETAILED ON ATTACHED EXHIBIT "A"), BY THE CITY OF LONG BEACH FROM ITS SHARE OF TIDELAND OIL REVENUES, TO CONSTRUCT AN OVERHEAD LANE MARKER SYSTEM IS IN ACCORDANCE WITH THE PROVISIONS OF CH. 138/54, 1ST E.S.; SAID DETERMINATION TO BE SUBJECT TO THE CONDITION THAT THE WORK CONFORM IN ESSENTIAL DETAIL TO THE PLANS AND BACKGROUND MATERIAL HERETO ONE SUBMITTED.

Attachment

Calendar Item 4 (2 pages)

CALENDAR ITEM

4/68
LBWO 10,204

4.

PROPOSED EXPENDITURE OF TIDELAND OIL REVENUE
CITY OF LONG BEACH

CAPITAL IMPROVEMENT PROJECT: Marine Stadium West

PRECEDING COMMISSION APPROVALS:

Date: July 20, 1965
Amount: \$1,790,000
Purpose: Construction of improvements, such as bleachers, boat-launch ramps, comfort stations, utilities, and beautification

THIS PROPOSAL:

Date: March 14, 1968
Amount: \$37,400
Purpose: Construction of an overhead lane marker system for intercollegiate crew races

Staff Analysis: Found reasonable

STATUTORY REFERENCE: Ch. 138/64, 1st E.S., Sect. 6(d)

OTHER PERTINENT INFORMATION: Details of project set forth on City Engineer Drawing No. B-2244, Sheets 1 through 12, with cost estimate

EXHIBITS:
"A" - Cost estimate
"B" - Vicinity sketch
"C" - Detail sketch
"D" - Photographs of site

IT IS RECOMMENDED THAT THE COMMISSION DETERMINE THAT THE EXPENDITURE PROPOSED AT MARINE STADIUM WEST OF APPROXIMATELY \$37,400 (AS DETAILED ON ATTACHED EXHIBIT "A"), BY THE CITY OF LONG BEACH FROM ITS SHARE OF TIDELAND OIL REVENUES, TO CONSTRUCT AN OVERHEAD LANE MARKER SYSTEM IS IN ACCORDANCE WITH THE PROVISIONS OF CH. 138/64, 1ST E.S.; SAID DETERMINATION TO BE SUBJECT TO THE CONDITION THAT THE WORK CONFORM IN ESSENTIAL DETAIL TO THE PLANS AND BACKGROUND MATERIAL HERETOFORE SUBMITTED.

Attachment: Exhibit "A"

EXHIBIT "A"

LONG BEACH CITY ESTIMATE
MARINE STADIUM
OVERHEAD LANE MARKER SYSTEM

REQUIREMENT:

Suspended cables at 1000 m., 1500 m., and 2012 m., lines to support 6 lane markers on each cable. Condition at 1000 m. line requires dolphin support or other special treatment.

PERMANENT FACILITY AS DESIGNED:

| | | | |
|----------------|--|--------------|-----------------|
| 5 | 40' steel poles w/flag mast & ladder at \$1000 ea. | \$5,000 | |
| 15 | 20' conc. piles at \$320 ea. in place | 4,800 | |
| 5 | P.C.C. footings at \$1000 | 5,000 | |
| 3 | Winches at \$1620 ea. | 4,860 | |
| 3 | Winch covers at \$200 ea. | 600 | |
| | Electric installation for winches L.S. | 340 | |
| 2100 Lin Ft | 5/8 galv. st'l cable at \$0.66 (in place) | 1,400 | |
| | Ladders, flagpole & misc. fittings for dolphin | <u>1,000</u> | |
| | Subtotal | | \$23,000 |
| 18 | Suspended lane markers at \$120 ea. (in place) | 2,160 | |
| 12 | Bridge mounted L.M. at \$120 | <u>1,440</u> | |
| | Subtotal | | \$ 3,600 |
| 1 | 3 pile conc. dolphin (Belmont float contract) | <u>7,400</u> | |
| | Total | | \$34,000 |
| | 10% contingency | | <u>3,400</u> |
| | TOTAL COST OVERHEAD LANE MARKER SYSTEM | | <u>\$37,400</u> |